Northbridge Industrial and Electrical Supply
Warehouse 6, Tierra Vista Estate, Carmona, Cavite

QUOTATION NO. **NBI-SQ-2026-511**

PRICE QUOTATION

SUPPLY AND DELIVERY OF ELECTRICAL MATERIALS

QUOTATION NO.	NBI-SQ-2026-511	**DATE**	04 November 2026
PROJECT CODE	SCP-26-EL-024	**VALID UNTIL**	04 December 2026
TO	Sierra Crest Construction & Development Corporation		
PROJECT	Cavite Materials Distribution Warehouse - Electrical Lighting and Small Power Fit-Out		
DELIVERY SITE	Barangay Langkaan II, Dasmariñas City, Cavite		
BOM / BOQ REF.	SCC-BOQ-2026-024		

I. ITEMIZED MATERIAL PRICE PROPOSAL

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
A. BRANCH CIRCUIT WIRING					
CV-EL-001	**THHN/THWN-2 copper branch conductor** 5.5 mm² stranded Cu, 600 V, red; series EconomyLine	m	600	₱56.46	₱33,876.00
CV-EL-002	**THHN/THWN-2 copper branch conductor** 5.5 mm² stranded Cu, 600 V, blue; series EconomyLine	m	600	₱59.09	₱35,454.00
CV-EL-003	**THHN/THWN-2 copper grounding conductor** 3.5 mm² stranded Cu, 600 V, green; series EconomyLine	m	850	₱34.19	₱29,061.50
CV-EL-004	**Liquid-tight flexible metallic conduit** 20 mm nominal diameter, polymer jacketed; series EconomyLine	m	100	₱142.00	₱14,200.00
B. RACEWAYS AND BOXES					
CV-EL-005	**uPVC electrical conduit** 20 mm nominal, heavy-duty, 3.0 m straight length; series EconomyLine	pc	240	₱117.00	₱28,080.00
CV-EL-006	**uPVC electrical conduit** 25 mm nominal, heavy-duty, 3.0 m straight length; series EconomyLine	pc	140	₱174.00	₱24,360.00
CV-EL-007	**uPVC 20 mm 90-degree elbow** Heavy-duty, solvent-weld type; series EconomyLine	pc	150	₱33.93	₱5,089.50
CV-EL-008	**uPVC 25 mm 90-degree elbow** Heavy-duty, solvent-weld type; series EconomyLine	pc	75	₱44.80	₱3,360.00
CV-EL-009	**PVC utility switch box** 50 x 100 mm (2 x 4 in), heavy-duty; series EconomyLine	pc	110	₱73.88	₱8,126.80
CV-EL-010	**PVC junction box** 100 x 100 mm (4 x 4 in), deep type with cover; series EconomyLine	pc	60	₱102.00	₱6,120.00
CV-EL-011	**Flexible conduit straight connector** 20 mm, liquid-tight, threaded; series EconomyLine	pc	90	₱80.91	₱7,281.90
C. DISTRIBUTION AND PROTECTION					
CV-EL-012	**MCB for power outlets** 2-pole, 16 A, 6 kA, DIN rail, 230 V; series EconomyLine	pc	25	₱807.00	₱20,175.00
CV-EL-013	**MCB for lighting circuits** 1-pole, 15 A, 6 kA, DIN rail, 230 V; series EconomyLine	pc	40	₱376.00	₱15,040.00
CV-EL-014	**Distribution panelboard assembly** 24 circuits, 3-pole main 100 A, copper busbar; series EconomyLine	set	2	₱23,712.00	₱47,424.00

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
D. LIGHTING FIXTURES					
CV-EL-015	**LED linear batten luminaire** 12 W, 6000 K, 220-240 V, surface-mounted; series EconomyLine	pc	110	₱588.00	₱64,680.00
CV-EL-016	**LED high-bay warehouse luminaire** 100 W, 5000 K, 220-240 V, IP65; series EconomyLine	pc	16	₱3,527.00	₱56,432.00
CV-EL-017	**LED emergency exit light** Battery-backed, minimum 90-minute operation; series EconomyLine	pc	16	₱1,353.00	₱21,648.00
E. SWITCHES AND RECEPTACLES					
CV-EL-018	**Modular wall switch** 2-gang, 16 A, 250 V, flush type; series EconomyLine	pc	42	₱392.00	₱16,464.00
CV-EL-019	**Duplex grounding convenience outlet** 16 A, 250 V with faceplate, flush type; series EconomyLine	pc	75	₱369.00	₱27,675.00
F. SUPPORTS AND GROUNDING					
CV-EL-020	**Copper-bonded grounding rod** 16 mm diameter x 2.4 m length; series EconomyLine	pc	6	₱1,618.00	₱9,708.00
CV-EL-021	**Ground rod clamp** Bronze, suitable for 16 mm grounding rod; series EconomyLine	pc	6	₱399.00	₱2,694.00
CV-EL-022	**Galvanized wireway cable tray** 150 x 50 mm, 2.4 m length, perforated; series EconomyLine	length	25	₱1,789.00	₱44,725.00
CV-EL-023	**Cable tray coupling kit** For 150 mm cable tray with fasteners; series EconomyLine	set	46	₱243.00	₱11,178.00
CV-EL-024	**Nylon cable tie pack** 300 mm long, 100 pieces per pack; series EconomyLine	pack	20	₱176.00	₱3,520.00

MATERIALS SUBTOTAL (EXCL. VAT)	₱536,372.70
TRADE DISCOUNT (2.0%)	-₱10,727.45
DELIVERY / FREIGHT	₱15,500.00
HANDLING / UNLOADING	₱2,300.00
NET TAXABLE AMOUNT	₱543,445.25
VALUE-ADDED TAX (12%)	₱65,213.43
TOTAL QUOTATION AMOUNT	₱608,658.68

II. COMMERCIAL TERMS AND CONDITIONS

Delivery lead time: 25 calendar days from receipt of payment confirmation.
Payment terms: 50% advance; 50% before delivery.
Quotation valid until: 04 December 2026. Prices are expressed in Philippine pesos.
Freight, handling, discount and VAT are itemized above; Quoted prices exclude site lifting and installation work.
The supplier shall deliver only the materials, quantities and ratings expressly indicated in the offered item schedule.

III. AUTHORIZED REPRESENTATIVE

Issued by:

_____

Justine R. Velasco

Sales Operations Head

Signature over printed name