NORTHLINE UTILITY ENGINEERING SERVICES

Mangaldan, Pangasinan, Philippines

BILL OF MATERIALS

Document No. NUE-BOM-2026-007

Date: 08 November 2026
Project Owner: Mr. Adrian S. Navarro
Project Site: Brgy. Baquioen, Sual, Pangasinan
Subject: Bill of materials and quantities

BILL OF MATERIALS / QUANTITIES

CONVERSION AND LINE EXTENSION

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE (PHP)	AMOUNT (PHP)
1	25 kVA amorphous distribution transformer, 7620/240 V	1	unit	85,400.00	85,400.00
2	Concrete utility pole, 35 ft, class 5	7	pcs	19,600.00	137,200.00
3	Bare ACSR conductor #2/0 AWG	329	m	67.00	22,043.00
4	Insulated conductor #2/0 AWG	329	m	190.00	62,510.00
5	Guy wire attachment, malleable	7	pcs	180.00	1,260.00
6	Concrete round anchor block	7	pcs	1,200.00	8,400.00
7	Eye bolt, oval, 5/8 x 12 in.	8	pcs	133.32	1,066.56
8	Machine bolt, 5/8 x 12 in.	4	pcs	71.28	285.12
9	Machine bolt, 1/2 x 6 in.	2	pcs	35.64	71.28
10	Secondary swinging clevis	5	pcs	115.00	575.00
11	Insulated suspension bracket	3	pcs	125.00	375.00
12	Tamperproof ground-rod clamp	7	pcs	39.60	277.20
13	Hot-line clamp	3	pcs	627.00	1,881.00
14	Loop dead-end clamp	8	pcs	76.56	612.48
15	Anchor rod bonding clamp, single eye	7	pcs	66.00	462.00
16	Dead-end strain clamp for ACSR conductors	2	pcs	470.00	940.00
17	Compression connector #6 - #1/0 ACSR	8	pcs	112.20	897.60
18	Compression connector #2/0 - #4/0 ACSR	6	pcs	165.00	990.00

Continued on next sheet - items 19 through 36.

NORTHLINE UTILITY ENGINEERING SERVICES

Mangaldan, Pangasinan, Philippines

BILL OF MATERIALS

Document No. NUE-BOM-2026-007

Date: 08 November 2026
Project Owner: Mr. Adrian S. Navarro
Project Site: Brgy. Baquioen, Sual, Pangasinan
Subject: Bill of materials and quantities

BILL OF MATERIALS / QUANTITIES

CONVERSION AND LINE EXTENSION

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE (PHP)	AMOUNT (PHP)
19	Combined cutout and lightning arrester	2	pcs	6,500.00	13,000.00
20	Fuse link, K-type	2	pcs	192.00	384.00
21	Galvanized ground rod, 5/8 x 10 ft	1	pcs	673.20	673.20
22	Three-strand iron grounding wire, 5/16 in.	200	ft	33.00	6,600.00
23	Seven-strand steel guy wire, 3/8 in.	150	ft	39.60	5,940.00
24	Six-inch clevis suspension insulator	8	pcs	396.00	3,168.00
25	Locknut, 5/8 in.	7	pcs	23.76	166.32
26	Conventional eye nut, 5/8 in.	1	pcs	114.84	114.84
27	Dummy plate	6	pcs	540.00	3,240.00
28	Two-point heavy-duty secondary rack with insulator	2	pcs	1,100.00	2,200.00
29	Spool insulator, 1-3/4 in.	2	pcs	32.40	64.80
30	Square washer, 4 x 4 in.	2	pcs	125.40	250.80
31	Washer, 2-1/4 x 2-1/4 in.	7	pcs	29.04	203.28
32	Primary jumper, #6 copper	6	m	300.00	1,800.00
33	Insulated secondary jumper, #2/0 copper	30	m	636.00	19,080.00
34	Transformer cluster hanger	2	pcs	1,020.00	2,040.00
35	Fuse cut-out mounting bracket	1	pcs	1,500.00	1,500.00
36	#2/0 conductor stirrup	2	pcs	633.60	1,267.20

SUBTOTAL OF ITEM EXTENSIONS — PHP 386,938.68

RECONCILIATION ALLOWANCE — PHP 399.00

MATERIAL COST PER PROJECT QUOTATION — **PHP 387,337.68**

The allowance reconciles the original summary and its 36 listed item extensions;
it is not an additional material quantity or new line item.
Prepared by: _____