NORTHLINE UTILITY ENGINEERING SERVICES

Mangaldan, Pangasinan, Philippines

QUOTATION

Document No. NUE-QUO-2026-007

Date: 08 November 2026
Project Owner: Mr. Adrian S. Navarro
Project Site: Brgy. Baquioen, Sual, Pangasinan
Subject: Quotation - distribution line extension & transformer installation

PROJECT QUOTATION

1. GENERAL SCOPE OF WORK

1.1 Erect 35-ft Class 5 concrete poles with supporting hardware.

1.2 String primary conductors from the point of tap to designated poles.

1.3 Install 25-kVA amorphous distribution transformer, 7620/240V, 60Hz.

1.4 Terminate secondary jumpers and complete service entrance connections.

2. PROJECT COST SUMMARY

2.1	Material Cost	PHP 387,337.68
2.2	Tools, Equipment & Labor	PHP 116,201.30
2.3	Mobilization and Consumables	PHP 10,000.00
2.4	VAT (as quoted)	PHP 0.00
TOTAL PROJECT COST		**PHP 513,538.98**

3. PAYMENT TERMS

40% upon acceptance of the quotation	PHP 205,415.59
60% upon completion of the works	PHP 308,123.39

4. MATERIALS PROCUREMENT AND LEAD TIME

Material delivery lead time: approximately 15 days from payment acceptance, subject to supplier availability and an agreed work schedule.

Quoted materials are detailed in document NUE-BOM-2026-007. Price validity: 20 calendar days from quotation date.

Authorized Signature

Printed Name / Position: _____

Date: 08 November 2026
Project Owner: Mr. Adrian S. Navarro
Project Site: Brgy. Baquioen, Sual, Pangasinan
Subject: Quotation - distribution line extension & transformer installation

GENERAL CONDITIONS AND SCOPE OF SERVICE

5. LABOR AND TECHNICAL SUPPORT

Electrical line works, pole setting, transformer installation, termination, testing, and technical coordination are covered by the labor and equipment allowance in Section 2.

6. COMMENCEMENT AND COMPLETION

Work shall commence on a schedule mutually agreed by the project owner and the contractor, after required materials and access are available.

7. WARRANTY

A one-year service and materials warranty against defects in workmanship and manufacturing, excluding force majeure, misuse, and unauthorized modification.

8. EXCLUSIONS

Authority permits, distribution utility charges, and unforeseen civil works not expressly stated in the bill of materials are excluded unless separately authorized.

9. APPLICABLE DOCUMENTS

This quotation shall be read together with the separate bill of materials, quantities, and agreed work specifications.

SUBMITTED BY

_____

Authorized Signature
Printed Name / Position: _____

Conforme: _____
Project owner / authorized representative