Pioneer MEP Distribution Services Corporation
Block 4, Unity Commercial District, Santa Rosa City, Laguna

QUOTATION NO. **PME-SQ-2026-179**

PRICE QUOTATION

SUPPLY AND DELIVERY OF ELECTRICAL MATERIALS

QUOTATION NO.	PME-SQ-2026-179	**DATE**	31 October 2026
PROJECT CODE	SCP-26-EL-024	**VALID UNTIL**	30 November 2026
TO	Sierra Crest Construction & Development Corporation		
PROJECT	Cavite Materials Distribution Warehouse - Electrical Lighting and Small Power Fit-Out		
DELIVERY SITE	Barangay Langkaan II, Dasmariñas City, Cavite		
BOM / BOQ REF.	SCC-BOQ-2026-024		

I. ITEMIZED MATERIAL PRICE PROPOSAL

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
A. BRANCH CIRCUIT WIRING					
CV-EL-001	**THHN/THWN-2 copper branch conductor** 5.5 mm² stranded Cu, 600 V, red; series ProCircuit	m	600	₱62.66	₱37,596.00
CV-EL-002	**THHN/THWN-2 copper branch conductor** 5.5 mm² stranded Cu, 600 V, blue; series ProCircuit	m	600	₱61.56	₱36,936.00
CV-EL-003	**THHN/THWN-2 copper grounding conductor** 3.5 mm² stranded Cu, 600 V, green; series ProCircuit	m	850	₱36.27	₱30,829.50
CV-EL-004	**Liquid-tight flexible metallic conduit** 20 mm nominal diameter, polymer jacketed; series ProCircuit	m	100	₱142.00	₱14,200.00
B. RACEWAYS AND BOXES					
CV-EL-005	**uPVC electrical conduit** 20 mm nominal, heavy-duty, 3.0 m straight length; series ProCircuit	pc	240	₱128.00	₱30,720.00
CV-EL-006	**uPVC electrical conduit** 25 mm nominal, heavy-duty, 3.0 m straight length; series ProCircuit	pc	140	₱180.00	₱25,200.00
CV-EL-007	**uPVC 20 mm 90-degree elbow** Heavy-duty, solvent-weld type; series ProCircuit	pc	150	₱35.66	₱5,349.00
CV-EL-008	**uPVC 25 mm 90-degree elbow** Heavy-duty, solvent-weld type; series ProCircuit	pc	75	₱44.23	₱3,317.25
CV-EL-009	**PVC utility switch box** 50 x 100 mm (2 x 4 in), heavy-duty; series ProCircuit	pc	110	₱80.45	₱8,849.50
CV-EL-010	**PVC junction box** 100 x 100 mm (4 x 4 in), deep type with cover; series ProCircuit	pc	60	₱114.00	₱6,840.00
CV-EL-011	**Flexible conduit straight connector** 20 mm, liquid-tight, threaded; series ProCircuit	pc	90	₱84.28	₱7,585.20
C. DISTRIBUTION AND PROTECTION					
CV-EL-012	**MCB for power outlets** 2-pole, 20 A, 6 kA, DIN rail, 230 V; series ProCircuit	pc	25	₱856.00	₱21,400.00
CV-EL-013	**MCB for lighting circuits** 1-pole, 15 A, 6 kA, DIN rail, 230 V; series ProCircuit	pc	40	₱374.00	₱14,960.00
CV-EL-014	**Distribution panelboard assembly** 24 circuits, 3-pole main 100 A, copper busbar; series ProCircuit	set	2	₱26,065.00	₱52,130.00
D. LIGHTING FIXTURES					
CV-EL-015	**LED linear batten luminaire** 18 W, 6000 K, 220-240 V, surface-mounted; series ProCircuit	pc	110	₱607.00	₱66,770.00

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
CV-EL-016	**LED high-bay warehouse luminaire** 100 W, 5000 K, 220-240 V, IP65; series ProCircuit	pc	22	₱3,707.00	₱81,554.00
CV-EL-017	**LED emergency exit light** Battery-backed, minimum 90-minute operation; series ProCircuit	pc	16	₱1,336.00	₱21,376.00
E. SWITCHES AND RECEPTACLES					
CV-EL-018	**Modular wall switch** 2-gang, 16 A, 250 V, flush type; series ProCircuit	pc	42	₱427.00	₱17,934.00
CV-EL-019	**Duplex grounding convenience outlet** 16 A, 250 V with faceplate, flush type; series ProCircuit	pc	75	₱410.00	₱30,750.00
F. SUPPORTS AND GROUNDING					
CV-EL-020	**Copper-bonded grounding rod** 16 mm diameter x 2.4 m length; series ProCircuit	pc	6	₱1,686.00	₱10,116.00
CV-EL-021	**Ground rod clamp** Bronze, suitable for 16 mm grounding rod; series ProCircuit	pc	6	₱423.00	₱2,538.00
CV-EL-022	**Galvanized wireway cable tray** 150 x 50 mm, 2.4 m length, perforated; series ProCircuit	length	25	₱1,780.00	₱44,500.00
CV-EL-023	**Cable tray coupling kit** For 150 mm cable tray with fasteners; series ProCircuit	set	46	₱267.00	₱12,282.00
CV-EL-024	**Nylon cable tie pack** 300 mm long, 100 pieces per pack; series ProCircuit	pack	20	₱182.00	₱3,640.00

MATERIALS SUBTOTAL (EXCL. VAT)	₱587,372.45
TRADE DISCOUNT (3.0%)	-₱17,621.17
DELIVERY / FREIGHT	₱24,000.00
HANDLING / UNLOADING	₱0.00
NET TAXABLE AMOUNT	₱593,751.28
VALUE-ADDED TAX (12%)	₱71,250.15
TOTAL QUOTATION AMOUNT	₱665,001.43

II. COMMERCIAL TERMS AND CONDITIONS

Delivery lead time: 7 calendar days for stocked items; 14 days for remaining items.
Payment terms: Net 30 days upon delivery and receipt of signed delivery note.
Quotation valid until: 30 November 2026. Prices are expressed in Philippine pesos.
Freight, handling, discount and VAT are itemized above; Includes consolidated delivery to the site on an agreed unloading date.
The supplier shall deliver only the materials, quantities and ratings expressly indicated in the offered item schedule.

III. AUTHORIZED REPRESENTATIVE

Issued by:

_____

Marielle P. Enriquez

Regional Sales Supervisor

Signature over printed name