Riverton Buildworks Corporation
3/F Balete Trade Center, Sumulong Avenue, Antipolo City, Rizal

BOM / BOQ NO. **RBC-BOM-2026-017**

BILL OF MATERIALS / BILL OF QUANTITIES

SCHEDULE OF ELECTRICAL MATERIAL REQUIREMENTS

PROJECT CODE	RIV-26-EL-017	**DATE**	26 October 2026
DOCUMENT NO.	RBC-BOM-2026-017	**REVISION**	00
PROJECT	Rizal Workers Dormitory - Main Feeder and Panelboard Rehabilitation		
LOCATION	Barangay San Roque, Antipolo City, Rizal		
CLIENT	Rizal Dormitory Holdings, Inc.		
SCOPE	Electrical feeder, main distribution equipment, conduit, supports and grounding materials		

I. ITEMIZED MATERIAL REQUIREMENTS

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	EST. UNIT COST (PHP)	EST. AMOUNT (PHP)
A. POWER CABLES AND CONDUCTORS					
RZ-EL-001	**THHN/THWN-2 copper feeder conductor** 250 mm², stranded Cu, 600 V, 90°C, black	m	30	₱3,480.00	₱104,400.00
RZ-EL-002	**THHN/THWN-2 copper feeder conductor** 125 mm², stranded Cu, 600 V, 90°C, black	m	40	₱1,700.00	₱68,000.00
RZ-EL-003	**THHN/THWN-2 grounding conductor** 50 mm², stranded Cu, 600 V, green	m	35	₱690.00	₱24,150.00
RZ-EL-004	**THHN/THWN-2 control conductor** 5.5 mm², stranded Cu, 600 V, red	m	90	₱82.00	₱7,380.00
B. POWER DISTRIBUTION					
RZ-EL-005	**Main molded-case circuit breaker** 3-pole, 400 A, 36 kA at 415 V, thermal-magnetic	unit	1	₱34,500.00	₱34,500.00
RZ-EL-006	**Feeder molded-case circuit breaker** 3-pole, 250 A, 25 kA at 415 V, thermal-magnetic	unit	1	₱19,600.00	₱19,600.00
RZ-EL-007	**Main distribution panelboard assembly** 800 x 600 x 250 mm, IP54 steel enclosure, Cu busbar	set	1	₱42,800.00	₱42,800.00
RZ-EL-008	**Current transformer set** 400/5 A, class 1.0, three-phase metering, 3 pcs/set	set	1	₱8,900.00	₱8,900.00
C. CONDUIT AND SUPPORTS					
RZ-EL-009	**Rigid steel conduit, galvanized** 75 mm (3 in) nominal, threaded, 3.0 m length	pc	2	₱2,690.00	₱5,380.00
RZ-EL-010	**Rigid steel conduit 90-degree elbow** 75 mm (3 in), galvanized, long-radius	pc	2	₱1,950.00	₱3,900.00
RZ-EL-011	**Rigid steel conduit coupling** 75 mm (3 in), threaded, galvanized	pc	4	₱390.00	₱1,560.00
RZ-EL-012	**Insulated conduit bushing** 75 mm (3 in), threaded, nylon insulated throat	pc	8	₱245.00	₱1,960.00
RZ-EL-013	**Galvanized cable tray** 300 x 50 mm, 2.4 m section, perforated	length	8	₱2,780.00	₱22,240.00
RZ-EL-014	**Cable tray splice plate kit** For 300 mm tray, two plates plus fasteners/set	set	14	₱270.00	₱3,780.00
RZ-EL-015	**Heavy-duty conduit clamp** 75 mm (3 in), galvanized steel	pc	12	₱165.00	₱1,980.00
D. TERMINATIONS AND GROUNDING					
RZ-EL-016	**Compression copper cable lug** For 250 mm² cable, M12 stud, tinned Cu	pc	16	₱290.00	₱4,640.00

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	EST. UNIT COST (PHP)	EST. AMOUNT (PHP)
RZ-EL-017	**Compression copper cable lug** For 125 mm² cable, M10 stud, tinned Cu	pc	16	₱182.00	₱2,912.00
RZ-EL-018	**Copper-bonded grounding rod** 16 mm diameter x 2.4 m length	pc	2	₱1,680.00	₱3,360.00
RZ-EL-019	**Heavy-duty grounding clamp** For 16 mm rod, bronze mechanical clamp	pc	2	₱415.00	₱830.00
RZ-EL-020	**Bare copper bonding jumper** 50 mm² stranded copper cable	m	10	₱745.00	₱7,450.00
E. MISCELLANEOUS MATERIALS					
RZ-EL-021	**Self-adhesive PVC electrical tape** 19 mm x 20 m roll, flame retardant, black	roll	6	₱92.00	₱552.00
RZ-EL-022	**Firestop sealant cartridge** 300 mL, intumescent, for conduit penetration	tube	8	₱690.00	₱5,520.00
RZ-EL-023	**Electrical hazard identification plate** Weather-resistant laminated, 150 x 100 mm	pc	10	₱125.00	₱1,250.00
RZ-EL-024	**IP54 galvanized junction box** 300 x 300 x 150 mm with gasketed cover	pc	2	₱3,100.00	₱6,200.00

ESTIMATED MATERIAL COST (EXCL. VAT)	₱383,244.00
PLANNING VAT ALLOWANCE (12%)	₱45,989.28
TOTAL MATERIALS COST ESTIMATE	₱429,233.28

II. PROCUREMENT BASIS

Quantities are for the electrical materials required for this project. Labor and installation are excluded from the schedule. Material ratings, dimensions and units constitute the basis for supplier quotation comparison. Estimated prices are for internal cost planning only.

III. PREPARATION AND APPROVAL

Prepared by:

Engr. Aileen P. Solis
Project Electrical Engineer

Checked by:

Engr. Mateo R. Dizon
Construction Manager

Approved by:

Engr. Celina T. Soriano
Project Director