Sierra Crest Construction & Development Corporation
4/F Pelican Business Court, Governor's Drive, General Trias City, Cavite

BOM / BOQ NO. **SCC-BOQ-2026-024**

BILL OF MATERIALS / BILL OF QUANTITIES

SCHEDULE OF ELECTRICAL MATERIAL REQUIREMENTS

PROJECT CODE	SCP-26-EL-024	**DATE**	28 October 2026
DOCUMENT NO.	SCC-BOQ-2026-024	**REVISION**	00
PROJECT	Cavite Materials Distribution Warehouse - Electrical Lighting and Small Power Fit-Out		
LOCATION	Barangay Langkaan II, Dasmariñas City, Cavite		
CLIENT	Cavite Freight & Storage Holdings, Inc.		
SCOPE	Branch-circuit wiring, conduit system, lighting, accessories, grounding and cable supports		

I. ITEMIZED MATERIAL REQUIREMENTS

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	EST. UNIT COST (PHP)	EST. AMOUNT (PHP)
A. BRANCH CIRCUIT WIRING					
CV-EL-001	**THHN/THWN-2 copper branch conductor** 5.5 mm² stranded Cu, 600 V, red	m	600	₱65.00	₱39,000.00
CV-EL-002	**THHN/THWN-2 copper branch conductor** 5.5 mm² stranded Cu, 600 V, blue	m	600	₱65.00	₱39,000.00
CV-EL-003	**THHN/THWN-2 copper grounding conductor** 3.5 mm² stranded Cu, 600 V, green	m	850	₱39.00	₱33,150.00
CV-EL-004	**Liquid-tight flexible metallic conduit** 20 mm nominal diameter, polymer jacketed	m	100	₱155.00	₱15,500.00
B. RACEWAYS AND BOXES					
CV-EL-005	**uPVC electrical conduit** 20 mm nominal, heavy-duty, 3.0 m straight length	pc	240	₱132.00	₱31,680.00
CV-EL-006	**uPVC electrical conduit** 25 mm nominal, heavy-duty, 3.0 m straight length	pc	140	₱188.00	₱26,320.00
CV-EL-007	**uPVC 20 mm 90-degree elbow** Heavy-duty, solvent-weld type	pc	150	₱38.00	₱5,700.00
CV-EL-008	**uPVC 25 mm 90-degree elbow** Heavy-duty, solvent-weld type	pc	75	₱48.00	₱3,600.00
CV-EL-009	**PVC utility switch box** 50 x 100 mm (2 x 4 in), heavy-duty	pc	110	₱82.00	₱9,020.00
CV-EL-010	**PVC junction box** 100 x 100 mm (4 x 4 in), deep type with cover	pc	60	₱118.00	₱7,080.00
CV-EL-011	**Flexible conduit straight connector** 20 mm, liquid-tight, threaded	pc	90	₱89.00	₱8,010.00
C. DISTRIBUTION AND PROTECTION					
CV-EL-012	**MCB for power outlets** 2-pole, 20 A, 6 kA, DIN rail, 230 V	pc	25	₱920.00	₱23,000.00
CV-EL-013	**MCB for lighting circuits** 1-pole, 15 A, 6 kA, DIN rail, 230 V	pc	40	₱410.00	₱16,400.00
CV-EL-014	**Distribution panelboard assembly** 24 circuits, 3-pole main 100 A, copper busbar	set	2	₱26,800.00	₱53,600.00
D. LIGHTING FIXTURES					
CV-EL-015	**LED linear batten luminaire** 18 W, 6000 K, 220-240 V, surface-mounted	pc	110	₱635.00	₱69,850.00
CV-EL-016	**LED high-bay warehouse luminaire** 100 W, 5000 K, 220-240 V, IP65	pc	22	₱3,950.00	₱86,900.00

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	EST. UNIT COST (PHP)	EST. AMOUNT (PHP)
CV-EL-017	**LED emergency exit light** Battery-backed, minimum 90-minute operation	pc	16	₱1,450.00	₱23,200.00
E. SWITCHES AND RECEPTACLES					
CV-EL-018	**Modular wall switch** 2-gang, 16 A, 250 V, flush type	pc	42	₱435.00	₱18,270.00
CV-EL-019	**Duplex grounding convenience outlet** 16 A, 250 V with faceplate, flush type	pc	75	₱425.00	₱31,875.00
F. SUPPORTS AND GROUNDING					
CV-EL-020	**Copper-bonded grounding rod** 16 mm diameter x 2.4 m length	pc	6	₱1,780.00	₱10,680.00
CV-EL-021	**Ground rod clamp** Bronze, suitable for 16 mm grounding rod	pc	6	₱455.00	₱2,730.00
CV-EL-022	**Galvanized wireway cable tray** 150 x 50 mm, 2.4 m length, perforated	length	25	₱1,950.00	₱48,750.00
CV-EL-023	**Cable tray coupling kit** For 150 mm cable tray with fasteners	set	46	₱275.00	₱12,650.00
CV-EL-024	**Nylon cable tie pack** 300 mm long, 100 pieces per pack	pack	20	₱190.00	₱3,800.00

ESTIMATED MATERIAL COST (EXCL. VAT)	₱619,765.00
PLANNING VAT ALLOWANCE (12%)	₱74,371.80
TOTAL MATERIALS COST ESTIMATE	₱694,136.80

II. PROCUREMENT BASIS

Quantities are for the electrical materials required for this project. Labor and installation are excluded from the schedule. Material ratings, dimensions and units constitute the basis for supplier quotation comparison. Estimated prices are for internal cost planning only.

III. PREPARATION AND APPROVAL

Prepared by:

Engr. Paolo M. Reyes
Electrical Design Coordinator

Checked by:

Engr. Therese L. Abad
Quantity Surveying Manager

Approved by:

Engr. Julius R. Fajardo
Project Manager