Tamarind Electrotechnical Supply Corporation
Unit 12, Marikina Trade Arcade, Marikina City, Metro Manila

QUOTATION NO. **TES-SQ-2026-114**

PRICE QUOTATION

SUPPLY AND DELIVERY OF ELECTRICAL MATERIALS

QUOTATION NO.	TES-SQ-2026-114	**DATE**	02 November 2026
PROJECT CODE	RIV-26-EL-017	**VALID UNTIL**	02 December 2026
TO	Riverton Buildworks Corporation		
PROJECT	Rizal Workers Dormitory - Main Feeder and Panelboard Rehabilitation		
DELIVERY SITE	Barangay San Roque, Antipolo City, Rizal		
BOM / BOQ REF.	RBC-BOM-2026-017		

I. ITEMIZED MATERIAL PRICE PROPOSAL

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
A. POWER CABLES AND CONDUCTORS					
RZ-EL-001	**THHN/THWN-2 copper feeder conductor** 250 mm², stranded Cu, 600 V, 90°C, black; series CoreLine	m	30	₱3,479.00	₱104,370.00
RZ-EL-002	**THHN/THWN-2 copper feeder conductor** 125 mm², stranded Cu, 600 V, 90°C, black; series CoreLine	m	40	₱1,624.00	₱64,960.00
RZ-EL-003	**THHN/THWN-2 grounding conductor** 50 mm², stranded Cu, 600 V, green; series CoreLine	m	35	₱684.00	₱23,940.00
RZ-EL-004	**THHN/THWN-2 control conductor** 5.5 mm², stranded Cu, 600 V, red; series CoreLine	m	90	₱77.63	₱6,986.70
B. POWER DISTRIBUTION					
RZ-EL-005	**Main molded-case circuit breaker** 3-pole, 400 A, 36 kA at 415 V, thermal-magnetic; series CoreLine	unit	1	₱33,879.00	₱33,879.00
RZ-EL-006	**Feeder molded-case circuit breaker** 3-pole, 250 A, 25 kA at 415 V, thermal-magnetic; series CoreLine	unit	1	₱19,940.00	₱19,940.00
RZ-EL-007	**Main distribution panelboard assembly** 800 x 600 x 250 mm, IP54 steel enclosure, Cu busbar; series CoreLine	set	1	₱41,651.00	₱41,651.00
RZ-EL-008	**Current transformer set** 400/5 A, class 1.0, three-phase metering, 3 pcs/set; series CoreLine	set	1	₱8,976.00	₱8,976.00
C. CONDUIT AND SUPPORTS					
RZ-EL-009	**Rigid steel conduit, galvanized** 75 mm (3 in) nominal, threaded, 3.0 m length; series CoreLine	pc	2	₱2,594.00	₱5,188.00
RZ-EL-010	**Rigid steel conduit 90-degree elbow** 75 mm (3 in), galvanized, long-radius; series CoreLine	pc	2	₱1,949.00	₱3,898.00
RZ-EL-011	**Rigid steel conduit coupling** 75 mm (3 in), threaded, galvanized; series CoreLine	pc	4	₱373.00	₱1,492.00
RZ-EL-012	**Insulated conduit bushing** 75 mm (3 in), threaded, nylon insulated throat; series CoreLine	pc	8	₱243.00	₱1,944.00
RZ-EL-013	**Galvanized cable tray** 300 x 50 mm, 2.4 m section, perforated; series CoreLine	length	8	₱2,632.00	₱21,056.00
RZ-EL-014	**Cable tray splice plate kit** For 300 mm tray, two plates plus fasteners/set; series CoreLine	set	14	₱265.00	₱3,710.00
RZ-EL-015	**Heavy-duty conduit clamp** 75 mm (3 in), galvanized steel; series CoreLine	pc	12	₱168.00	₱2,016.00

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
D. TERMINATIONS AND GROUNDING					
RZ-EL-016	**Compression copper cable lug** For 250 mm² cable, M12 stud, tinned Cu; series CoreLine	pc	16	₱282.00	₱4,512.00
RZ-EL-017	**Compression copper cable lug** For 125 mm² cable, M10 stud, tinned Cu; series CoreLine	pc	16	₱184.00	₱2,944.00
RZ-EL-018	**Copper-bonded grounding rod** 16 mm diameter x 2.4 m length; series CoreLine	pc	2	₱1,620.00	₱3,240.00
RZ-EL-019	**Heavy-duty grounding clamp** For 16 mm rod, bronze mechanical clamp; series CoreLine	pc	2	₱415.00	₱830.00
RZ-EL-020	**Bare copper bonding jumper** 50 mm² stranded copper cable; series CoreLine	m	10	₱712.00	₱7,120.00
E. MISCELLANEOUS MATERIALS					
RZ-EL-021	**Self-adhesive PVC electrical tape** 19 mm x 20 m roll, flame retardant, black; series CoreLine	roll	6	₱91.16	₱546.96
RZ-EL-022	**Firestop sealant cartridge** 300 mL, intumescent, for conduit penetration; series CoreLine	tube	8	₱653.00	₱5,224.00
RZ-EL-023	**Electrical hazard identification plate** Weather-resistant laminated, 150 x 100 mm; series CoreLine	pc	10	₱123.00	₱1,230.00
RZ-EL-024	**IP54 galvanized junction box** 300 x 300 x 150 mm with gasketed cover; series CoreLine	pc	2	₱3,154.00	₱6,308.00

MATERIALS SUBTOTAL (EXCL. VAT)	₱375,961.66
TRADE DISCOUNT (1.5%)	-₱5,639.42
DELIVERY / FREIGHT	₱3,800.00
HANDLING / UNLOADING	₱0.00
NET TAXABLE AMOUNT	₱374,122.24
VALUE-ADDED TAX (12%)	₱44,894.67
TOTAL QUOTATION AMOUNT	₱419,016.91

II. COMMERCIAL TERMS AND CONDITIONS

Delivery lead time: 14 calendar days from receipt of approved PO.
Payment terms: 40% advance payment; 60% prior to release.
Quotation valid until: 02 December 2026. Prices are expressed in Philippine pesos.
Freight, handling, discount and VAT are itemized above; Material delivery to project site; partial deliveries subject to written approval.
The supplier shall deliver only the materials, quantities and ratings expressly indicated in the offered item schedule.

III. AUTHORIZED REPRESENTATIVE

Issued by:

_____

Renato C. Valdez

Commercial Sales Manager

Signature over printed name