VENTRALINE ENGINEERING & CONSTRUCTION

Ligao City, Albay, Philippines

BILL OF QUANTITIES

Document No. VEC-BOQ-2026-018

Project Name: Dormitory Electrical Rehabilitation

Project Site: Sorsogon City, Sorsogon

Client / Owner: Sorsogon Residential Facilities Cooperative

Quotation Date: 08 November 2026

Project Duration: 30 calendar days

SCHEDULE A - MATERIALS AND INSTALLATION

NO.	DESCRIPTION / SPECIFICATION	QTY	UNIT	UNIT RATE MATERIAL	UNIT RATE LABOR	TOTAL MATERIAL	TOTAL LABOR	LINE TOTAL (PHP)
PANELBOARD AND CIRCUIT BREAKERS								
1	Panelboard assembly; 400AT / 250AT / 100AT, 3P breakers; copper busbar	1	pcs	128,500.00	44,975.00	128,500.00	44,975.00	173,475.00
ROUGHING-INS AND FITTINGS								
2	3-in. rigid steel conduit	2	pcs	2,650.00	927.50	5,300.00	1,855.00	7,155.00
3	3-in. LB conduit body	1	pc	875.00	306.25	875.00	306.25	1,181.25
4	3-in. locknut and bushing	1	pc	85.00	29.75	85.00	29.75	114.75
5	3-in. two-hole metal clamp	6	pcs	32.00	11.20	192.00	67.20	259.20
6	3-in. weatherhead	1	unit	395.00	138.25	395.00	138.25	533.25
7	5/16-in. expansion bolt	12	pcs	55.00	19.25	660.00	231.00	891.00
8	3/8-in. expansion bolt	4	pcs	72.00	25.20	288.00	100.80	388.80
WIRES AND CABLES								
9	250 mm2 THHN-2 copper conductor	30	m	3,100.00	1,085.00	93,000.00	32,550.00	125,550.00
10	125 mm2 THHN-2 copper conductor	40	m	1,795.00	628.25	71,800.00	25,130.00	96,930.00
11	30 mm2 THHN-2 copper conductor	50	m	375.00	131.25	18,750.00	6,562.50	25,312.50
12	Electrical insulating tape	6	pcs	75.00	26.25	450.00	157.50	607.50
13	Rubber insulating tape	6	pcs	255.00	89.25	1,530.00	535.50	2,065.50
14	325-500 mm2 solderless split-bolt connector	6	pcs	3,850.00	1,347.50	23,100.00	8,085.00	31,185.00

MATERIALS TOTAL **PHP 344,925.00**

Installation cost is shown alongside materials for reference to the project work quantities.

VENTRALINE ENGINEERING & CONSTRUCTION

Ligao City, Albay, Philippines

BILL OF QUANTITIES

Document No. VEC-BOQ-2026-018

Project Name: Dormitory Electrical Rehabilitation

Project Site: Sorsogon City, Sorsogon

Client / Owner: Sorsogon Residential Facilities Cooperative

Quotation Date: 08 November 2026

Project Duration: 30 calendar days

SCHEDULE B - SITE SERVICES AND RECONCILIATION

NO.	DESCRIPTION / SPECIFICATION	QTY	UNIT	UNIT RATE MATERIAL	UNIT RATE LABOR	TOTAL MATERIAL	TOTAL LABOR	LINE TOTAL (PHP)
MOBILIZATION / DEMOBILIZATION								
15	Site mobilization and demobilization	1	lot	-	5,000.00	-	5,000.00	5,000.00
REMOVAL OF EXISTING DEFECTIVE WORKS								
16	Removal of defective wires, conduits, fittings and panelboard	1	lot	-	10,000.00	-	10,000.00	10,000.00
TERMINATION WORKS								
17	Service and panelboard conductor termination	1	lot	-	3,000.00	-	3,000.00	3,000.00
TESTING AND COMMISSIONING								
18	Electrical testing, functional checks and commissioning	1	lot	-	2,000.00	-	2,000.00	2,000.00
OCCUPATIONAL SAFETY & HEALTH								
19	Safety controls and site compliance provisions	1	lot	-	4,856.49	-	4,856.49	4,856.49

COST RECONCILIATION

Material extensions	PHP 344,925.00
Labor + work-only services	PHP 145,580.24
Detailed direct cost	PHP 490,505.24
Contractor margin and other charges	PHP 82,560.29
TOTAL CONTRACT PRICE	**PHP 573,065.53**

Authorized Signature

Printed Name / Position: _____