Verdant Power & Industrial Trading
Luna Industrial Park, Barangay Paliparan, Dasmariñas City, Cavite

QUOTATION NO. **VPS-SQ-2026-086**

PRICE QUOTATION

SUPPLY AND DELIVERY OF ELECTRICAL MATERIALS

QUOTATION NO.	VPS-SQ-2026-086	**DATE**	02 October 2026
PROJECT CODE	RIV-26-EL-017	**VALID UNTIL**	31 October 2026
TO	Riverton Buildworks Corporation		
PROJECT	Rizal Workers Dormitory - Main Feeder and Panelboard Rehabilitation		
DELIVERY SITE	Barangay San Roque, Antipolo City, Rizal		
BOM / BOQ REF.	RBC-BOM-2026-017		

I. ITEMIZED MATERIAL PRICE PROPOSAL

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
A. POWER CABLES AND CONDUCTORS					
RZ-EL-001	**THHN/THWN-2 copper feeder conductor** 250 mm², stranded Cu, 600 V, 90°C, black; series SupplyCore	m	30	₱3,283.00	₱98,490.00
RZ-EL-002	**THHN/THWN-2 copper feeder conductor** 125 mm², stranded Cu, 600 V, 90°C, black; series SupplyCore	m	40	₱1,560.00	₱62,400.00
RZ-EL-003	**THHN/THWN-2 grounding conductor** 50 mm², stranded Cu, 600 V, green; series SupplyCore	m	35	₱669.00	₱23,415.00
RZ-EL-004	**THHN/THWN-2 control conductor** 5.5 mm², stranded Cu, 600 V, red; series SupplyCore	m	90	₱77.36	₱6,962.40
B. POWER DISTRIBUTION					
RZ-EL-005	**Main molded-case circuit breaker** 3-pole, 400 A, 36 kA at 415 V, thermal-magnetic; series SupplyCore	unit	1	₱31,662.00	₱31,662.00
RZ-EL-006	**Feeder molded-case circuit breaker** 3-pole, 250 A, 25 kA at 415 V, thermal-magnetic; series SupplyCore	unit	1	₱18,995.00	₱18,995.00
RZ-EL-007	**Main distribution panelboard assembly** 800 x 600 x 250 mm, IP54 steel enclosure, Cu busbar; series SupplyCore	set	1	₱40,379.00	₱40,379.00
RZ-EL-008	**Current transformer set** 400/5 A, class 1.0, three-phase metering, 3 pcs/set; series SupplyCore	set	1	₱8,168.00	₱8,168.00
C. CONDUIT AND SUPPORTS					
RZ-EL-009	**Rigid steel conduit, galvanized** 75 mm (3 in) nominal, threaded, 3.0 m length; series SupplyCore	pc	2	₱2,607.00	₱5,214.00
RZ-EL-010	**Rigid steel conduit 90-degree elbow** 75 mm (3 in), galvanized, long-radius; series SupplyCore	pc	2	₱1,840.00	₱3,680.00
RZ-EL-011	**Rigid steel conduit coupling** 75 mm (3 in), threaded, galvanized; series SupplyCore	pc	4	₱358.00	₱1,432.00
RZ-EL-012	**Insulated conduit bushing** 75 mm (3 in), threaded, nylon insulated throat; series SupplyCore	pc	8	₱237.00	₱1,896.00
RZ-EL-013	**Galvanized cable tray** 300 x 50 mm, 2.4 m section, perforated; series SupplyCore	length	8	₱2,623.00	₱20,984.00
RZ-EL-014	**Cable tray splice plate kit** For 300 mm tray, two plates plus fasteners/set; series SupplyCore	set	14	₱248.00	₱3,472.00

ITEM NO.	DESCRIPTION / MATERIAL SPECIFICATION	UNIT	QTY	UNIT PRICE (PHP)	AMOUNT (PHP)
RZ-EL-015	**Heavy-duty conduit clamp** 75 mm (3 in), galvanized steel; series SupplyCore	pc	12	₱160.00	₱1,920.00
D. TERMINATIONS AND GROUNDING					
RZ-EL-016	**Compression copper cable lug** For 250 mm² cable, M12 stud, tinned Cu; series SupplyCore	pc	16	₱274.00	₱4,384.00
RZ-EL-016	**Compression copper cable lug** For 250 mm² cable, M12 stud, tinned Cu; series SupplyCore	pc	4	₱274.00	₱1,096.00
RZ-EL-017	**Compression copper cable lug** For 125 mm² cable, M10 stud, tinned Cu; series SupplyCore	pc	16	₱167.00	₱2,672.00
RZ-EL-018	**Copper-bonded grounding rod** 16 mm diameter x 2.4 m length; series SupplyCore	pc	2	₱1,628.00	₱3,256.00
RZ-EL-019	**Heavy-duty grounding clamp** For 16 mm rod, bronze mechanical clamp; series SupplyCore	pc	2	₱392.00	₱784.00
RZ-EL-020	**Bare copper bonding jumper** 50 mm² stranded copper cable; series SupplyCore	m	10	₱684.00	₱6,840.00
E. MISCELLANEOUS MATERIALS					
RZ-EL-021	**Self-adhesive PVC electrical tape** 19 mm x 20 m roll, flame retardant, black; series SupplyCore	roll	6	₱89.16	₱534.96
RZ-EL-022	**Firestop sealant cartridge** 300 mL, intumescent, for conduit penetration; series SupplyCore	tube	8	₱651.00	₱5,208.00
RZ-EL-023	**Electrical hazard identification plate** Weather-resistant laminated, 150 x 100 mm; series SupplyCore	pc	10	₱115.00	₱1,150.00
RZ-EL-024	**IP54 galvanized junction box** 300 x 300 x 150 mm with gasketed cover; series SupplyCore	pc	2	₱3,004.00	₱6,008.00

MATERIALS SUBTOTAL (EXCL. VAT)	₱361,002.36
TRADE DISCOUNT (0%)	₱0.00
DELIVERY / FREIGHT	₱6,500.00
HANDLING / UNLOADING	₱0.00
NET TAXABLE AMOUNT	₱367,502.36
VALUE-ADDED TAX (12%)	₱44,100.28
TOTAL QUOTATION AMOUNT	₱411,602.64

II. COMMERCIAL TERMS AND CONDITIONS

Delivery lead time: 20 working days after order confirmation.
Payment terms: 30% reservation; 70% before dispatch.
Quotation valid until: 31 October 2026. Prices are expressed in Philippine pesos.
Freight, handling, discount and VAT are itemized above; Prices fixed only within the validity period indicated above.
The supplier shall deliver only the materials, quantities and ratings expressly indicated in the offered item schedule.

III. AUTHORIZED REPRESENTATIVE

Issued by:

_____

Irene M. Santiago

Bid and Sales Supervisor

Signature over printed name